

Chapter 2: Interior Identification

Table of Contents

2.03		Sign Family Overview
2.06	ID.01	Primary Department ID, Horizontal
2.07	ID.01S	Primary Department ID, Horizontal Suspended
2.08	ID.01	Additional Layout Examples
2.09	ID.02	Primary Department ID, Vertical
2.10	ID.02F	Primary Department ID, Vertical Frosted
2.11	ID.02	Additional Layout Examples
2.12	ID.03	Primary Department ID, Dimensional Letters
2.13	ID.03	Additional Layout Examples
2.14	ID.04	Specialty Department Arrival Logo
2.15	ID.05	Main Lobby Arrival Logo
2.16	ID.05	Additional Approved Logos
2.17	ID.06	Elevator Lobby Level ID
2.18	ID.07	Feature Amenity ID
2.19	ID.10	Building Entry ID, Public
2.20	ID.10	Additional Layout Examples
2.21	ID.11	Building Entry ID, Restricted
2.22	ID.12	Building Legacy ID
2.23	ID.12-G	Building Legacy ID Building Graphics
2.24	ID.20	Tactile Room ID
2.25	ID.21	Tactile Room ID, Sequencing
2.26	ID.21	Additional Layouts
2.27	ID.22	Tactile ID with Department Zip Code
2.28	ID.23	Tactile ID for Amenities and Essential Services
2.29	ID.24	Tactile Office ID
2.30	ID.25	Tactile Room ID, Non-Public Access
2.31	ID.26	Tactile Restroom ID
2.32	ID.26	Additional Layout Examples
2.33	ID.27	Restroom Door ID Symbol, Gender Neutral
2.34	ID.28	Restroom Door ID Symbol, Women
2.35	ID.29	Restroom Door ID Symbol, Men
2.36	ID.30	Patient Observation Room ID, Static
2.37	ID.31	Baby Changing Station
2.38	ID.40.1	Amenities and Essential Services Flag ID, 10"
2.39	ID.40.2	Amenities and Essential Services Flag ID, 12"
2.40	ID.41.1	Department Zip Code Flag ID, 10"
2.41	ID.41.2	Department Zip Code Flag ID, 13"
2.42	ID.43C	Large Overhead ID, Ceiling Mounted
2.43	ID.43C	Additional Example Layouts


Chapter 2: Interior Identification

Table of Contents

2.44	ID.43F	Large Overhead ID, Flag Mounted
2.45	ID.43F	Additional Example Layouts
2.46	ID.44	Small Overhead ID, Wall Mounted
2.47	ID.44C	Small Overhead ID, Ceiling Mounted
2.48	ID.44F	Small Overhead ID, Flag Mounted
2.49	ID.50	Maintenance ID Tag
2.50	ID.51	Cubicle Workstation ID
2.51	ID.52	Locker Number Tag

Interior Identification

Sign Family Overview



ID.01 / ID.01S
Primary Department ID, Horizontal (typical, preferred)



ID.03
Primary Department ID,
Dimensional Letters



ID.04
Specialty Department Arrival Logo



ID.05
Main Lobby Arrival Logo




ID.07
Feature Amenity ID



ID.06
Elevator Lobby Level ID




ID.11
Building Entry ID, Restricted




ID.02
Primary
Department ID,
Vertical




ID.02F
Primary
Department ID,
Vertical Frosted




ID.10
Building Entry ID, Public




ID.12
Building Legacy ID




ID.20
Tactile Room ID




ID.21
Tactile Room ID, Sequencing



ID.22
Tactile ID with
Department Zip Code



ID.23
Tactile ID for Amenities
and Essential Services




ID.24
Tactile Office ID




ID.25
Tactile Room ID,
Non-Public Access




ID.26
Tactile Restroom ID



ID.27
Restroom Door ID Symbol,
Gender-Neutral




ID.28
Restroom Door ID Symbol,
Women



ID.29
Restroom Door ID Symbol,
Men

Interior Identification

Sign Family Overview



ID.30
Patient Observation Room ID,
Static




ID.31
Baby Changing Station




ID.40.1/ID.40.2
Amenities and Essential
Services Flag ID
(2 sizes available)



ID.41.1/ID.41.2
Department Zip Code
Flag ID
(2 sizes available)



ID.43C
Large Overhead ID,
Ceiling Mounted



ID.43F
Large Overhead ID,
Flag Mounted



ID.44
Small Overhead ID,
Wall Mounted




ID.44C
Small Overhead ID,
Ceiling Mounted



ID.44F
Small Overhead ID,
Flag Mounted



ID.50
Maintenance ID Tag



ID.51
Cubicle Workstation ID



ID.52
Locker ID Tag

Interior Identification

ID.01

Primary Department ID, Horizontal

Usage

- Operationally required sign to identify patient care departments and essential services (i.e. Admissions, Pharmacy).
- All patient care departments within the same building must use the same style Primary Department Identification.

Placement

- Wall mounted at the exterior of the department or destination adjacent to the entry door.

Components

- (A) Panel: 1/4" thick non-glare acrylic, subsurface painted with clear returns and smooth, finished milled edges
- (B) Symbol: 1/4" thick non-glare acrylic, subsurface painted symbol and background color with clear returns and smooth, finished milled edges
 - Typeface: Proxima Nova Extra Condensed Medium
- (C) Department/Destination Name: 1/4" thick acrylic letters, painted all visible surfaces, mounted flush to (A).
 - Typeface: Proxima Nova Regular
- (D) Accent: 7/8" x 3/8" architectural aluminum u-channel, fine satin finish with horizontal grain to match M3

- (E) Spacer Panel: 1/4" thick acrylic, inset 2" from top and sides, concealed from view to create standoff spacer

Colors & Materials

See Chapter 1: Universal Standards for detailed color and material specifications.

(C1) White Wonder

(C3) Vanadium Gray

(C4) UC Davis Blue


(M3) Brushed Aluminum

Additional Signage Required

- ID.22 Tactile ID with Zip Code or ID.23 Tactile ID with Symbol
- ID.40 Amenities and Essential Services Flag ID or ID.41 Department Zip Code Flag ID

Installation

- See Appendix A, Drawing FD.55 for approved standard fabrication and installation detail.
- **Verification of ceiling and wall conditions, in addition to coordination with the architect on sign placement, is required with nurse call lights, exit signs, other code-related signs, and obstructions.**
- **The need for additional structural support to be verified on project specific basis.**



Interior Identification

ID.01S

Primary Department ID, Horizontal Suspended

Usage

- Operationally required sign to identify patient care departments and essential services (i.e. Admissions, Pharmacy).
- Suspended detail when wall space is unavailable or the condition is an open threshold.

Placement

- Suspended within the entryway of the department, center to the threshold.
- A detailed location plan is to be provided to the FP&D Signage Program Representative for review and approval.

Components

- (A) Panel: 1/4" thick acrylic, surface painted all exposed surfaces
- (B) Symbol: 1/4" thick non-glare acrylic, subsurface painted symbol and background color with clear returns and smooth, finished milled edges
 - Typeface: Proxima Nova Extra Condensed Medium
- (C) Department/Destination Name: 1/4" thick acrylic letters, painted all visible surfaces, mounted flush to (A).
 - Typeface: Proxima Nova Regular
- (D) Accent: 7/8" x 3/8" architectural aluminum u-channel, fine satin finish with horizontal grain to match M3

- (E) Suspension Cables: aluminum rod with panel gripper and mounting plate—Gyford standoff systems part numbers #WL-AUBM, #WL-A64-250 Satin aluminum, vertical grain (finish to match M3)

Colors & Materials

References as noted below. See Chapter 1: Universal Standards for specifications.


- (C1) White Wonder
- (C3) Vanadium Gray
- (C4) UC Davis Blue
- (M3) Brushed Aluminum


Additional Signage Required

- ID.22 Tactile ID with Zip Code or ID.23 Tactile ID with Symbol
- ID.40 Amenities and Essential Services Flag ID or ID.41 Department Zip Code Flag ID


Installation

- See Appendix A, Drawing FD.45 for approved standard fabrication and installation detail.
- Verification of ceiling and wall conditions, in addition to coordination with the architect on sign placement, is required with nurse call lights, exit signs, other code-related signs, and obstructions.
- The need for additional structural support to be verified on project specific basis.






Single Line Message with 3-digit Zip Code



Single Line Message with 2-digit Zip Code



2 1/2" Text Height for Welcome, Admissions, Registration, or Guest Relations Only

Interior Identification

ID.02

Primary Department ID, Vertical

Usage

- Operationally required sign to identify patient care departments and essential services (i.e. Admissions, Pharmacy).

Placement

- Sign is to be placed on the wall or portal adjacent the primary arrival to the department.
- Elevations or renderings to be provided to FP&D Signage Program Representative for review and approval.

Components

- (A) Panel: 3/4" thick non-glare acrylic with subsurface painted background; clear returns, smooth, finished milled edges
- (B) Symbol: cut vinyl with clear matte overlamine
 - Typeface: Proxima Nova Extra Condensed Medium
- (C) Department/Destination Name: cut vinyl with clear matte overlamine
 - Typeface: Proxima Nova Regular

- (D) Brackets/Accents: 2" high extruded aluminum C-channel attached to wall with matching L-bracket; all seams grind and welded

Colors & Materials

See Chapter 1: Universal Standards for detailed color and material specifications.



- | | | |
|-------------------|-----------------------|------------------|
| (C1) White Wonder | (V1) Matte White | (V3) Nimbus Grey |
| (V9) Vivid Blue | (M3) Brushed Aluminum | |

Additional Signage Required

- ID.22 Tactile ID with Zip Code or ID.23 Tactile ID with Symbol
- ID.40 Amenities and Essential Services Flag ID or ID.41 Department Zip Code Flag ID

Installation

- See Appendix A, Drawing FD.56 for approved standard fabrication and installation detail.
- Sign is anticipated to weigh over 20 lbs. Additional architecturally integrated and coordinated backing is required for hospital facilities per HCAI, and is recommended for consideration at all facilities.
- Final location and mounting height to be coordinated with architectural conditions for each sign location.



Interior Identification

ID.02F

Usage

- Operationally required sign to identify patient care departments and essential services (i.e. Admissions, Pharmacy).
- Frosted option to be used when wall finish has a specialized texture or super graphic.

Placement

- Sign is to be placed on the wall or portal adjacent the primary arrival to the department.
- Elevations or renderings to be provided to FP&D Signage Program Representative for review and approval.

Components

- (A) Panel: 3/4" thick P95 acrylic with subsurface vinyl background; polished edges, no paint, diffused effect of background wall
- (B) Symbol: cut vinyl with clear matte overlamine
 - Typeface: Proxima Nova Condensed Medium
- (C) Department/Destination Name: cut vinyl with clear matte overlamine
 - Typeface: Proxima Nova Regular

- (D) Brackets/Accents: 2" high extruded aluminum C-channel attached to wall with matching L-bracket; all seams grind and welded

Colors & Materials

See Chapter 1: Universal Standards for detailed color and material specifications.


- | | | |
|---------------------------|------------------|-----------------------|
| (M6) Plexiglass Clear P95 | (V1) Matte White | (V3) Nimbus Grey |
| (V7) Milky White Film | (V9) Vivid Blue | (M3) Brushed Aluminum |

Additional Signage Required


- ID.22 Tactile ID with Zip Code or ID.23 Tactile ID with Symbol
- ID.40 Amenities and Essential Services Flag ID or ID.41 Department Zip Code Flag ID

Installation

- See Appendix A, Drawing FD.56 for approved standard fabrication and installation detail.
- **Sign is anticipated to weigh over 20 lbs. Additional architecturally integrated and coordinated backing is required for hospital facilities per HCAI, and is recommended for consideration at all facilities**
- **Final location and mounting height to be coordinated with architectural conditions for each sign location. .**



NOTE:
The color of the copy shall contrast with the wall color and finish.
Final copy and graphics colors to be confirmed in field, prior to fabrication.





Double Line Message
with 3-digit Zip Code
Scale: 3/4" = 1'-0"



Single Line Message
with 4-digit Zip Code



Single Line Message with
Universal Wayfinding Symbol



Double Line Message
with 4-digit Zip Code

Interior Identification

ID.03

Primary Department ID, Dimensional Letters

Usage

- Used under special consideration only.
- Primarily considered for surgery suites or other departments where the elevators may open directly into the lobby/waiting area of that department, and there is no appropriate conditions for either ID.01 or ID.02 Primary Department Identification signs.

Placement

- Sign is to be placed centered behind registration, guest relations desk, or other location as approved by FP&D Signage Program Representative.
- Elevations and location plan are to be provided to the FP&D Signage Program Representative for review and approval.

Components

- Ⓐ Letters: 1/2" flat cut acrylic department name, painted on all visible surfaces
 - Typeface: Proxima Nova Regular
- Ⓑ Symbol: 1/2" flat cut acrylic universal wayfinding symbol or department zip code, subsurface painted text or symbol and background color; clear returns with smooth, finished milled edges

Colors & Materials

See Chapter 1: Universal Standards for detailed color and material specifications.



Ⓒ1 White Wonder

Ⓒ3 Vanadium Gray


Ⓒ4 UC Davis Blue

Installation

- See Appendix A, Drawings FD.05 and FD.06 for approved standard fabrication and installation details.



Installation Context
Scale: 3/16" = 1'-0"



Single Line Layout

Interior Identification

ID.04

Specialty Department Arrival Logo

Usage

- This sign is used at specialty departments with the permission of UC Davis Health Public Affairs and Marketing only.

Placement

- Architect or signage consultant to provide sign location plan and elevation for review and approval by FP&D Signage Program Representative in collaboration with Public Affairs and Marketing.

Components

- Ⓐ Logo: 1/4" flat cut acrylic department logo, painted on all visible surfaces
 - Typeface: Proxima Nova Light

Colors & Materials



See Chapter 1: Universal Standards for detailed color and material specifications.

Ⓒ4 UC Davis Blue

Ⓒ5 UC Davis Gold

Installation

- See Appendix A, Drawing FD.06 for approved standard fabrication and installation detail.
- Drawing FD.05 is an acceptable alternative if pins are not appropriate for the final stroke width of the department name once final size is determined.



Interior Identification

ID.05

Main Lobby Arrival Logo

Usage

- Operationally required sign within arrival lobby of all patient care facilities.

Placement

- Behind greeter's desk or other impactful location visible upon arrival into the space.
- Architect or signage consultant to provide sign location plan and elevation for review and approval of size, finish, and placement by FP&D Signage Program Representative in collaboration with Public Affairs and Marketing.

Components

- (A) Logo: fabricated aluminum logo, surface painted C4 (preferred), C1 or C3 to contrast with the finished wall. Return depth varies by total logo height.
 - 1" returns for 18" tall logo
 - 2" returns for 19" to 35" logo
 - 3" returns for 36" tall logo and up
- All projects to use UC Davis Health logo as shown in the layout below, unless a sub-brand logo has been provided by Public Affairs and Marketing (shown on next page).

- NOTE:** No logos other than those shown in the Brand Standards document should be used to represent any UC Davis Health entity without prior approval from Public Affairs & Marketing. Should a new or additional logo be required, Public Affairs & Marketing will create the new logo and make it available in digital format. Co-branding (UC Davis Health logo appearing in conjunction with another business entity) is not allowable without written approval by Public Affairs & Marketing.

Colors & Materials

See Chapter 1: Universal Standards for detailed color and material specifications.



- (C1) White Wonder (C3) Vanadium Gray (C4) UC Davis Blue

Additional Signage Required

- ID.40 Amenities and Essential Services Flag ID when installed at a Guest Relations desk

Installation

- See Appendix A, Drawing FD.07 for approved standard fabrication and installation detail.



**UCDAVIS
HEALTH**

**UCDAVIS
HEALTH**

Use of Two Color Logo to Be Reviewed and
Approved by Marketing

**UCDAVIS
HEALTH**

**MEDICAL
CENTER**

**UCDAVIS
HEALTH**

**CHILDREN'S
HOSPITAL**

**UCDAVIS
HEALTH**

**SCHOOL OF
MEDICINE**

**UCDAVIS
HEALTH**

**MIND
INSTITUTE**

**UCDAVIS
HEALTH**

**BETTY IRENE MOORE
SCHOOL OF NURSING**

**UCDAVIS
HEALTH**

**COMPREHENSIVE
CANCER CENTER**



White Logo and Graphics to be Used on Dark Walls

Interior Identification

ID.06

Elevator Lobby Level ID

Usage

- Operationally required sign to identify floor level within elevator lobbies.

Placement

- The sign to be placed 5' AFF to the bottom of the numbers, and located on left or right side of the elevation if available.
- Architect or signage consultant to provide sign location plan and elevation for review and approval of finish and placement by FP&D Signage Program Representative.

Components

- (A) Number: 1/4" thick acrylic number, painted on all visible surfaces; paint color to be chosen based on what is appropriate to provide sufficient contrast with the background
 - Typeface: Proxima Nova Medium

Colors & Materials

See Chapter 1: Universal Standards for detailed color and material specifications.

(C1) White Wonder

(C3) Vanadium Gray

Installation


- See Appendix A, Drawing FD.06 for approved standard fabrication and installation detail.



Front View
Scale: 1" = 1'-0"



Side View



Installation Context
Scale: 3/16" = 1'

Interior Identification

ID.07

Feature Amenity ID

Usage

- Feature identification for patient amenities to be used when architecturally and contextually appropriate.

Placement

- The sign and its components (symbol and text) are to be sized and placed in a manner that is appropriate for the condition which best responds to patient wayfinding needs.

Components

- Ⓐ Letters: flat cut acrylic destination name, painted on all visible surfaces
 - 1/4" thick for cap heights less than 3"
 - 1/2" thick for cap heights 3" and above
 - Typeface: Proxima Nova Regular

- Ⓑ Symbol: flat cut acrylic, subsurface painted symbol and background color with clear returns and smooth, finished milled edges; same thickness as letters based on height
 - **NOTE: This sign correlates with the wayfinding signage standards and uses the universal wayfinding symbols as defined within this document. It is not meant to determine the logo for individual entities.**



Colors & Materials

See Chapter 1: Universal Standards for detailed color and material specifications.

Ⓒ1 White Wonder Ⓒ3 Vanadium Gray Ⓒ14 Amenities Green

Installation

- See Appendix A, Drawing FD.05 or FD.06 for approved standard fabrication and installation detail.



Interior Identification

ID.10

Building Entry ID, Public

Usage

- Operationally required to identify main entry points leading into all UC Davis Health facilities.
- The only facilities which may omit this sign are those which have security concerns, such as pharmacy warehouse, data facilities, or similar.

Placement

- On the exterior-most arrival door of the facility; do not repeat this sign within a vestibule.

Components

- ① Cut vinyl copy and graphics
 - **UC Davis Health Logo:** When a UC Davis Health Sub-Brand logo lockup has been approved and provided, it should be used in place of the stand alone UC Davis Health logo shown below. Review and approval from Public Affairs and Marketing is required.
 - Facility Name Typeface: Proxima Nova Semibold

Colors & Materials

See Chapter 1: Universal Standards for detailed color and material specifications.

V1 Matte White

Additional Signs Required


- CD.01 Entry Notices Vinyl


Additional User Requested Signs

- IN.22 Vinyl Information (hours) – discretionary


Installation

- See Appendix A, Drawing FD.01 for approved standard fabrication and installation detail.







Message Example for Building Without Pre-Approved Sub-Brand Logo



Message Example for Building With Pre-Approved Sub-Brand Logo



Message Example for Building With Three Line Message



Message Example Single Door Layout

Interior Identification

ID.11

Building Entry ID, Restricted

Usage

- Operationally required sign to identify controlled access entrance points into the building.

Placement

- Sign is located on exterior doors. See installation context.

Components

- Ⓐ Cut vinyl copy
 - Typeface: Proxima Nova Semibold

Colors & Materials

See Chapter 1: Universal Standards for detailed color and material specifications.

V1 Matte White

V4 Geranium

Installation


- See Appendix A, Drawing FD.01 for approved standard fabrication and installation detail.



Front View
Scale: 1 1/2" = 1'-0"



Front View
Scale: 3" = 1'-0"



Installation Context
Scale: 3/16" = 1'-0"

Installation Context
Scale: 3/16" = 1'-0"

Interior Identification

ID.12

Building Legacy ID

Usage

- This sign type is used to commemorate a UC Davis Health building.

Placement

- Place at the main lobby in a conspicuous space near the Information Desk and adjacent to the LEED plaque, if applicable.
- Final placement to be coordinated with FP&D Signage Program Representative.

Components

- (A) Cast Bronze plaque as manufactured by Matthews Architectural Products or equivalent
 - 5/8" thick plaque with single line border raised .1" from textured background.
 - Pebbled background texture
 - Provide low-gloss lacquer protective coating to prevent oxidizing
 - Raised Typography: Proxima Nova Extra Condensed Regular and Italic

- (B) Building graphics. Artwork shall be an integral component of the cast plaque, specified as Imagecast. The appearance of the building graphic is contingent upon the artwork provided by the FP&D Signage Program Representative.
 - See ID.12-G for additional graphic details
- (C) Installation: Utilize manufacturer recommended hardware and installation methods per wall conditions.

Colors & Materials


See Chapter 1: Universal Standards for detailed color and material specifications.

(M12) Satin Bronze

(M13) Dark Bronze M-313

Installation

See Appendix A, Drawing FD.35 for approved standard fabrication and installation detail.



Interior Identification

ID.12-G

Building Legacy ID Building Graphics

Building Graphics

Building graphics to be specified as Imagecast.


- Artwork should be cropped to desired shape/outline.
- White represents a raised area, black represents a recessed area.

Imagecast

- Grayscale artwork in CMYK color mode. Submit both edited file, cropped to desired outline, and unedited photo.
- Image should be a minimum of 300 DPI.
- Adobe Illustrator format required for full artwork with linked building image; building image format can be .psd, .tiff, .jpg or .ai.



Imagecast Plaque



Imagecast Artwork

Manufacturer will adjust artwork for raised and recessed areas

Usage

- Fulfills ADA requirement for tactile text and Braille sign to identify permanent rooms and spaces.
- Use in patient and staff front-of-house areas for rooms such as workrooms, break rooms, conference rooms, etc.

Placement

- See installation context. If space is unavailable, refer to CBC and provide alternate placement plans to FP&D Signage Program Representative.

Components

- (A) Panel: 1/8" thick non-glare acrylic
 - Finish: subsurface painted and with ADA compliant matte clear coat over finished sign face
 - Sides: no paint with clean routed edges
- (B) Text: ADA compliant UV cured dimensionally printed tactile lettering raised 1/32" above panel face with smooth edges; lettering color to be printed to match specified color
 - Typefaces:
Room Number – Proxima Nova Regular
Room Name – Proxima Nova Medium
- (C) California Grade 2 UV cured clear dimensionally printed Braille

- (D) Aluminum Laminate: 1/16" thick
 - Finish: satin brushed horizontal grain with eased edges

Additional Optional Signs

- IN.10A Lettersize Insert Holder

Additional User Requested Signs

Ambulatory Care Clinics:

- IN.21 Patient Room Status Flags
Procedure :

- IN.21 Patient Room Status Flags
- IN.11 Insert Holder for Laminated Insert
In-Patient Beds / ICU / ED:

- Use ID.30 with integrated patient precautions unless otherwise approved by Nurse Manager in collaboration with FP&D Signage Program Representative.


Colors & Materials

See Chapter 1: Universal Standards for detailed color and material specifications.

- (C1) White Wonder (D3) PMS Cool Gray 10C (D21) Clear
- (M3) Brushed Aluminum

Installation

- See Appendix A, Drawing FD.15 for approved standard fabrication and installation detail.



Interior Identification

ID.21

Tactile Room ID, Sequencing

Usage

- Fulfills ADA requirement for tactile text and Braille sign to identify permanent rooms and spaces.
- Use at outpatient care rooms system wide.

Placement

- See installation context. If space is unavailable, refer to CBC and provide alternate placement plans to FP&D Signage Program Representative.

Components

- (A) Panel: 1/8" thick non-glare acrylic
 - Finish: subsurface painted and with ADA compliant matte clear coat over finished sign face
 - Sides: no paint with clean routed edges
- (B) Text: ADA compliant UV cured dimensionally printed tactile lettering raised 1/32" above panel face with smooth edges; lettering color to be printed to match specified color
 - Typeface: Proxima Nova Medium
- (C) California Grade 2 UV cured clear dimensionally printed Braille
- (D) Aluminum Laminate: 1/16" thick
 - Finish: satin brushed horizontal grain with eased edges

Additional Signs Required

- ID.44(F or C) Small Overhead ID (optional)
- ID.50 Maintenance ID Tag

Additional User Requested Signs

Ambulatory Care Clinics:

- IN.21 Patient Room Status Flags

Procedure :

- IN.21 Patient Room Status Flags
- IN.11 Insert Holder for Laminated Insert

In-Patient Beds / ICU / ED:

- Use ID.30 with integrated patient precautions unless otherwise approved by Nurse Manager in collaboration with FP&D Signage Program Representative.



Colors & Materials

See Chapter 1: Universal Standards for detailed color and material specifications.


- (C1) White Wonder
- (D3) PMS Cool Gray 10C
- (D21) Clear
- (M3) Brushed Aluminum

Installation

- See Appendix A, Drawing FD.15 for approved standard fabrication and installation detail.




Installation Context
Scale: 3/16" = 1'-0"




Patient Bed, Single




Patient Bed, Multiple




Birthing Suite




Procedure



Operating Room



Exam / Treatment



Accessible Room

Interior Identification

ID.24

Tactile Office ID

Usage

- Fulfills ADA requirement for tactile text and Braille sign to identify permanent rooms and spaces.
- Use at single or double occupancy offices.
- For greater occupancies, use sign type ID.20.

Placement

- See installation context. If space is unavailable, refer to CBC and provide alternate placement plans to FP&D Signage Program Representative.

Components

- (A) Front Panel: 1/8" thick non-glare acrylic with routed thumb notch
 - Finish: subsurface painted and with ADA compliant matte clear coat over finished sign face
 - Sides: no paint with clean routed edges
 - Window: remains clear for changeable insert
- (B) Text: ADA compliant UV cured dimensionally printed tactile lettering raised 1/32" above panel face with smooth edges; lettering color to be printed to match specified color
 - Typefaces:
Room Number – Proxima Nova Regular
Room Name – Proxima Nova Medium

- (C) California Grade 2 UV cured clear dimensionally printed Braille
- (D) Aluminum Laminate: 1/16" thick
 - Horizontal grain with eased edges
- (E) Back Panel: 3/16" thick acrylic backer, with milled out pocket (smooth edges with no visible milled markings) and routed thumb notch
 - Finish: subsurface painted
 - Sides: no paint with clean routed edges
- (F) Insert: 8 1/2" x 3" 80lb matte white cardstock with digitally printed copy
 - Typeface: Proxima Nova Regular


Colors & Materials

See Chapter 1: Universal Standards for detailed color and material specifications.

- | | | |
|-----------------------|------------------------|-------------|
| (C1) White Wonder | (D3) PMS Cool Gray 10C | (D21) Clear |
| (M3) Brushed Aluminum | (M7) 80lb Cardstock | |

Installation

- See Appendix A, Drawing FD.21 for approved standard fabrication and installation detail.



Interior Identification

ID.25

Tactile Room ID, Non-Public Access

Usage

- Fulfills ADA requirement for tactile text and Braille sign to identify permanent rooms and spaces.
- Use at all back-of-house rooms such as utility rooms, storage, mechanical rooms, etc.
- Preferred sign type and size for Non-Public Access identification.

Placement

- See installation context. If space is unavailable, refer to CBC and provide alternate placement plans to FP&D Signage Program Representative.

Components

- (A) Panel: 1/8" thick non-glare acrylic
 - Finish: subsurface painted and with ADA compliant matte clear coat over finished sign face
 - Sides: no paint with clean routed edges

- (B) Text: ADA compliant UV cured dimensionally printed tactile lettering raised 1/32" above panel face with smooth edges; lettering color to be printed to match specified color
 - Typefaces:
 - Room Number – Proxima Nova Regular
 - Room Name – Proxima Nova Medium
- (C) California Grade 2 UV cured clear dimensionally printed Braille


Colors & Materials

See Chapter 1: Universal Standards for detailed color and material specifications.

(C1) White Wonder (D3) PMS Cool Gray 10C (D21) Clear

Installation

- See Appendix A, Drawing FD.15 for approved standard fabrication and installation detail.



Interior Identification

ID.26

Tactile Restroom ID

Usage

- Fulfills ADA requirement for tactile text and Braille sign to identify permanent rooms and spaces.
- Use at all restrooms, locker rooms, lactation rooms, and shower facilities.

Placement

- See installation context. If space is unavailable, refer to CBC and provide alternate placement plans to FP&D Signage Program Representative.

Components

- (A) Panel: 1/8" thick non-glare acrylic
 - Finish: subsurface painted and with ADA compliant matte clear coat over finished sign face
 - Sides: no paint with clean routed edges
- (B) Text/Symbol: ADA compliant UV cured dimensionally printed tactile lettering raised 1/32" above panel face with smooth edges; lettering color to be printed to match specified color
 - Typeface: Proxima Nova Medium

- (C) California Grade 2 UV cured clear dimensionally printed Braille
- (D) Aluminum Laminate: 1/16" thick
 - Finish: satin brushed horizontal grain with eased edges

Colors & Materials

See Chapter 1: Universal Standards for detailed color and material specifications.



- (C1) White Wonder
- (D3) PMS Cool Gray 10C
- (D21) Clear
- (M3) Brushed Aluminum

Additional Signs Required


- ID.40(A or B) Amenities or Essential Services Flag ID (for public facilities only)
- ID.50 Maintenance Tag
- IN.10 (for Lactation Rooms only, locate sign on door)
- ID.31 (for rooms with a baby changing station)

Installation


- See Appendix A, Drawing FD.15 for approved standard fabrication and installation detail.




Typical - All-Gender




Non-accessible Women's




Non-accessible Men's




Accessible All-Gender




Accessible Women's




Accessible Men's




Accessible All-Gender, Staff




Accessible Women's, Staff




Accessible Men's, Staff




Locker Room




Accessible Women's Locker Room




Accessible Men's Locker Room



Lactation Room



Shower



Interior Identification

ID.27

Restroom Door ID Symbol, Gender Neutral

Usage

- CBC required sign to identify gender neutral restrooms.

Placement

- Sign is to be placed on the exterior of the door leading into the restroom facility.

Components

- (A) Circle Panel: 1/4" thick non-glare acrylic with 1/16" chamfered edge; subsurface painted with clear returns
- (B) Triangle Panel: 1/4" thick non-glare acrylic with 1/4" radius and 1/16" chamfered edge; subsurface painted with clear returns

Colors & Materials


See Chapter 1: Universal Standards for detailed color and material specifications.

(C1) White Wonder


(C3) Vanadium Gray

Installation


- See Appendix A, Drawing FD.30 for approved standard fabrication and installation detail.




Dark Door Colorway




Scale: 3/16"=1'-0"



Light Door Colorway
Scale: 3"=1'-0"



Side



Installation Context
Scale: 3/16" = 1'-0"

Interior Identification

ID.28

Restroom Door ID Symbol, Women

Usage

- CBC required sign to identify women's restrooms.

Placement

- Sign is to be placed on the exterior of the door leading into the restroom facility.

Components

- (A) Panel: 1/4" thick non-glare acrylic with 1/16" chamfered edge; subsurface painted with clear returns

Colors & Materials




See Chapter 1: Universal Standards for detailed color and material specifications.

(C1) White Wonder

(C3) Vanadium Gray

Installation

- See Appendix A, Drawing FD.30 for approved standard fabrication and installation detail.



Interior Identification

ID.29

Restroom Door ID Symbol, Men

Usage

- CBC required sign to identify men's restrooms.

Placement

- Sign is to be placed on the exterior of the door leading into the restroom facility.

Components

- Ⓐ Panel: 1/4" thick non-glare acrylic with 1/4" radius and 1/16" chamfered edge; subsurface painted with clear returns

Colors & Materials



See Chapter 1: Universal Standards for detailed color and material specifications

Ⓒ1 White Wonder

Ⓒ3 Vanadium Gray

Installation

- See Appendix A, Drawing FD.30 for approved standard fabrication and installation detail.



Interior Identification

ID.30

Patient Observation Room ID, Static

Usage

- Fulfills ADA requirement for tactile text and Braille sign to identify permanent rooms and spaces.
- Operationally required for In-patient care rooms and critical care units such as the ED and PACU.

Placement

- See installation context. If space is unavailable, refer to CBC and provide alternate placement plans to FP&D Signage Program Representative.

Components

Sign is a Howard Industries Patient Focused Sign with the following specifications:

- (A) Panel: 1/8" thick non-glare acrylic
 - Finish: subsurface painted and with ADA compliant matte clear coat over finished sign face
 - Sides: no paint with clean routed edges
- (B) Text: ADA compliant UV cured dimensionally printed tactile lettering raised 1/32" above panel face with smooth edges; lettering color to be printed to match specified color
 - Typeface: Proxima Nova Medium
- (C) California Grade 2 UV cured clear dimensionally printed Braille
- (D) Aluminum Laminate: 1/16" thick
 - Finish: satin brushed horizontal grain with eased edges
- (E) Acrylic Literature Holder: Uline model number S-18606 or approved equal

- (F) Pull Tabs, Left: UC Davis Health approved standard isolation pull tab messages and colors to comply with policy printouts. Messages and colors may not change without prior review and approval by FP&D Signage Program Representative.
- (G) Pull Tabs, Right: customizable pull tabs based on department needs; typical messages and colors shown; sign consultant or architect to review options with end-user for final selection.

Additional Signs Required

- ID.50 Maintenance Tag

Additional User Requested Signs

IN-PATIENT / PACU / ED:

- IN.10B Insert Holder, Half Letter Size
- ID.44 Small Overhead ID, Wall Mounted
- ID.44(F) Small Overhead ID, Flag Mounted



Colors & Materials

See Chapter 1: Universal Standards for detailed color and material specifications.

- (C1) White Wonder
- (D3) PMS Cool Gray 10C
- (D21) Clear
- (M3) Brushed Aluminum

Installation


- Wall Mounting: Mechanically fastened to finished wall per instruction provided by Howard Industries
- Glass Mounting: VHB and silicone adhesive per instructions provided by Howard Industries. First surface glass backup to be provided as shown in Drawing FD.15.



Howard Industries Colors

- | | |
|--------------|--------|
| Orange | Blue |
| Passion Pink | Grey |
| Bright Green | Teal |
| Purple | Yellow |
| Bright White | Black |

UC Davis Health to provide reasonable accommodations for employees requiring access to interactive signage elements installed 48" AFF.



Interior Identification

ID.31

Baby Changing Station

Usage

- This sign type is used to identify a room with a baby changing station.

Placement

- Place above corresponding room identification sign.

Components

- Ⓐ Panel: 1/8" thick non-glare acrylic
 - Finish: subsurface painted
 - Sides: no paint with clean routed edges

- Ⓑ Graphics: subsurface digital print
 - Typeface: Proxima Nova Medium



Colors & Materials

References as noted below. See Chapter 1: Universal Standards for specifications.

- Ⓒ1 White Wonder
- Ⓓ3 PMS Cool Gray 10C

Installation

- See Appendix A, Drawing FD.10 for approved standard fabrication and installation detail.



Interior Identification

ID.40.1

Amenities and Essential Services Flag ID, 10"

Usage

- Operationally required to identify amenities and essential services relevant to creating a ease of patient experience.
- This size option is to be used for higher ceilings with a maximum height of 9 feet.

Placement

- Adjacent to door, threshold, desk, or relevant equipment perpendicular to the path of travel; if referenced amenity is not adjacent to path of travel, signage to be placement to be evaluated based on best needs for patient wayfinding.

Components

- (A) Bracket: Johnson Plastics Plus Simply Corridor and Ceiling Bracket, Item #SBCC39SS; satin silver finish
- (B) Panel: 1/8" thick opaque white acrylic
 - Finish: painted all visible surfaces
 - Graphics: surface painted


Colors & Materials

See Chapter 1: Universal Standards for detailed color and material specifications.


(C1) White Wonder (C4) UC Davis Blue (C14) Amenities Green

Installation


- See Appendix A, Drawing FD.50 for approved standard fabrication and installation detail.
- Verification of ceiling and wall conditions, in addition to coordination with the architect on sign placement, is required with nurse call lights, exit signs, other code-related signs, and obstructions.
- The need for additional structural support to be verified on project specific basis.



Front View (Back View Similar)
Scale: 1 1/2"=1'-0"




(side B)



(side A)

Alternate Colors for Amenities
See Chapter 1 for additional
Universal Wayfinding Symbols



Installation Context
Scale: 3/16" = 1'-0"

Interior Identification

ID.40.2

Usage

- Operationally required to identify amenities and essential services relevant to creating a ease of patient experience.
- This size option is to be used for higher ceilings with a minimum height of 9 feet.

Placement

- Adjacent to door, threshold, desk, or relevant equipment perpendicular to the path of travel; if referenced amenity is not adjacent to path of travel, signage to be placement to be evaluated based on best needs for patient wayfinding.

Components

- (A) Bracket: Johnson Plastics Plus Simply Corridor and Ceiling Bracket, Item #SBCC39SS; satin silver finish
- (B) Panel: 1/8" thick opaque white acrylic
 - Finish: painted all visible surfaces
 - Graphics: surface painted

Amenities and Essential Services Flag ID, 12"


Colors & Materials

See Chapter 1: Universal Standards for detailed color and material specifications.

- (C1) White Wonder (C4) UC Davis Blue (C14) Amenities Green

Installation

- See Appendix A, Drawing FD.50 for approved standard fabrication and installation detail.
- Verification of ceiling and wall conditions, in addition to coordination with the architect on sign placement, is required with nurse call lights, exit signs, other code-related signs, and obstructions.
- The need for additional structural support to be verified on project specific basis.



Interior Identification

ID.41.1

Department Zip Code Flag ID, 10"

Usage

- Operationally required to supplement ID.01 or ID.02 Primary Department Identification signs.
- This size option is to be used for higher ceilings with a maximum height of 9 feet.

Placement

- Adjacent to doors or entry portals to the department within clear view of path of travel.

Components

- (A) Bracket: Johnson Plastics Plus Simply Corridor and Ceiling Bracket, Item #SBCC39SS; satin silver finish
- (B) Panel: 1/8" thick opaque white acrylic
 - Finish: painted all visible surfaces
 - Graphics: surface painted
 - Typeface: Proxima Nova Extra Condensed Medium



Colors & Materials

See Chapter 1: Universal Standards for detailed color and material specifications.

(C1) White Wonder (C4) UC Davis Blue

Installation

- See Appendix A, Drawing FD.50 for approved standard fabrication and installation detail.
- Verification of ceiling and wall conditions, in addition to coordination with the architect on sign placement, is required with nurse call lights, exit signs, other code-related signs, and obstructions.
- The need for additional structural support to be verified on project specific basis.



Interior Identification

ID.41.2

Department Zip Code Flag ID, 13"

Usage

- Operationally required to supplement ID.01 or ID.02 Primary Department Identification signs
- This size option is to be used for higher ceilings with a minimum height of 9 feet.

Placement

- Adjacent to doors or entry portals to the department within clear view of path of travel.

Components

- ① Bracket: Johnson Plastics Plus Simply Corridor and Ceiling Bracket, Item #SBCC39SS; satin silver finish
- ② Panel: 1/8" thick opaque white acrylic
 - Finish: painted all visible surfaces
 - Graphics: surface painted
 - Typeface: Proxima Nova Extra Condensed Medium

Colors & Materials



See Chapter 1: Universal Standards for detailed color and material specifications.

C1 White Wonder

 UC Davis Blue

Installation

- See Appendix A, Drawing FD.50 for approved standard fabrication and installation detail.
- Verification of ceiling and wall conditions, in addition to coordination with the architect on sign placement, is required with nurse call lights, exit signs, other code-related signs, and obstructions.
- The need for additional structural support to be verified on project specific basis.



Installation Context
Scale: 3/16" = 1'-0"

Interior Identification

ID.43C

Large Overhead ID, Ceiling Mounted

Usage

- Operationally required to identify Nurse/Medical Assistant/Care Team Stations within units. May be used as an alternate to ID.43F.
- Additional uses are discretionary; architect or signage consultant to confirm operational needs with end user.

Placement

- Center aligned with station, perpendicular to the path of travel.
- Location plan to be provided to FP&D Signage Program Representative for review of placement for alternate functions.

Components

- (A) Bracket: Johnson Plastics Plus Simply Corridor and Ceiling Bracket, Item #SBCC39SS; satin silver finish
- (B) Panel: 1/8" thick opaque white acrylic
 - Finish: painted all visible surfaces
 - Graphics: surface UV cured direct digital print
 - Typeface: Proxima Nova Condensed Regular

Colors & Materials



See Chapter 1: Universal Standards for detailed color and material specifications.


C1 White Wonder

 PMS Cool Gray 10C


Installation

- See Appendix A, Drawing FD.41 for approved standard fabrication and installation detail.
- Verification of ceiling and wall conditions, in addition to coordination with the architect on sign placement, is required with nurse call lights, exit signs, other code-related signs, and obstructions.
- The need for additional structural support to be verified on project specific basis.







Three Line Layout
Maximum Characters Allowed:
Approximately 10 per line




Two Line Layout
Maximum Characters Allowed:
Approximately 10 per line




Two Line Station Layout
Maximum Characters Allowed:
Line 1 - Approximately 10 per line
Line 2 - Approximately 5 per line



Two Line Pod Layout



Two Line Station Layout



Two Line Pod Layout

Interior Identification

ID.43F

Large Overhead ID, Flag Mounted

Usage

- Operationally required to identify Nurse/Medical Assistant/Care Team Stations within units. May be used as an alternate to ID.43C.
- Additional uses are discretionary; architect or signage consultant to confirm operational needs with end user.

Placement

- Center aligned with station, perpendicular to the path of travel.
- Location plan to be provided to FP&D Signage Program Representative for review of placement for alternate functions.

Components

- (A) Bracket: Johnson Plastics Plus Simply Corridor and Ceiling Bracket, Item #SBCC39SS; satin silver finish
- (B) Panel: 1/8" thick opaque white acrylic
 - Finish: painted all visible surfaces
 - Graphics: surface UV cured direct digital print
 - Typeface: Proxima Nova Condensed Regular

Colors & Materials



See Chapter 1: Universal Standards for detailed color and material specifications.


C1 White Wonder

D3 PMS Cool Gray 10C


Installation

- See Appendix A, Drawing FD.50 for approved standard fabrication and installation detail.
- **Verification of ceiling and wall conditions, in addition to coordination with the architect on sign placement, is required with nurse call lights, exit signs, other code-related signs, and obstructions.**
- **The need for additional structural support to be verified on project specific basis.**







Three Line Layout - Side A
Maximum Characters Allowed:
Approximately 10 per line




Three Line Layout - Side B




Two Line Layout - Side A
Maximum Characters Allowed:
Approximately 10 per line



Two Line Layout - Side B



Two Line Station/Pod Layout - Side A
Maximum Characters Allowed:
Line 1 - Approximately 10 per line
Line 2 - Approximately 5 per line



Two Line Station/Pod Layout - Side B

Interior Identification

ID.44

Small Overhead ID, Wall Mounted

Usage

- Operationally required for patient bed identification. May be used as an alternate to, or in conjunction with, ID.44C or ID.44F. End-user confirmation required.
- May be used for alternative functions.

Placement

- Center aligned with patient bed, when space permitting. Alternative placement requires coordination with end-user.
- Location plan to be provided to FP&D Signage Program Representative for review of placement for alternate functions.

Components

- Ⓐ Panel: 1/8" non-glare acrylic, subsurface digitally printed copy with subsurface painted background; clear returns with smooth, finished milled edges
 - Typeface: Proxima Nova Condensed Regular

Colors & Materials


See Chapter 1: Universal Standards for detailed color and material specifications.

Ⓒ1 White Wonder

Ⓓ3 PMS Cool Gray 10C

Installation

- See Appendix A, Drawing FD.10 approved standard fabrication and installation detail.



Interior Identification

ID.44C

Small Overhead ID, Ceiling Mounted

Usage

- Operationally required for patient bed identification. May be used as an alternate to ID.44F. End-user confirmation required.
- Operationally required when rooms are signed with ID.21, ID.30, or ID. 31. ID.44F may be used as an alternate.
- May be used for alternative functions.

Placement

- Center aligned with patient bed, perpendicular to medical staff path of travel upon room entry.
- Center aligned with corresponding room ID when used as described above..
- Location plan to be provided to FP&D Signage Program Representative for review of placement for alternate functions.

Components

- (A) Bracket: Johnson Plastics Plus Simply Corridor and Ceiling Bracket, Item #SBCC39SS
 - Finish: satin silver finish
 - Length: to span the length of the sign edge
- (B) Panel: 1/8" thick opaque white acrylic
 - Finish: painted all visible surfaces
 - Graphics: surface UV cured direct digital print
 - Typeface: Proxima Nova Condensed Regular

Colors & Materials


See Chapter 1: Universal Standards for detailed color and material specifications.

(C1) White Wonder


(D3) PMS Cool Gray 10C

Installation


- See Appendix A, Drawing FD.41 for approved standard fabrication and installation detail.
- Verification of ceiling and wall conditions, in addition to coordination with the architect on sign placement, is required with nurse call lights, exit signs, other code-related signs, and obstructions.
- The need for additional structural support to be verified on project specific basis.




Alternate Layout



Front View (Back View Similar)
Scale: 3"=1'-0"



Side



Installation Context
Scale: 3/16" = 1'-0"

Interior Identification

ID.44F

Small Overhead ID, Flag Mounted

Usage

- Operationally required for patient bed identification. May be used as an alternate to ID.44C. End-user confirmation required.
- May be used for alternative functions.

Placement

- Center aligned with corresponding room ID when used as described above.
- Location plan to be provided to FP&D Signage Program Representative for review of placement for alternate functions.

Components

- (A) Bracket: Johnson Plastics Plus Simply Corridor and Ceiling Bracket, Item #SBCC39SS
 - Finish: satin silver finish
 - Length: to span the length of the sign edge
- (B) Panel: 1/8" thick opaque white acrylic
 - Finish: painted all visible surfaces
 - Graphics: surface UV cured direct digital print
 - Typeface: Proxima Nova Condensed Regular

Colors & Materials


See Chapter 1: Universal Standards for detailed color and material specifications.

C1 White Wonder


D3 PMS Cool Gray 10C

Installation


- See Appendix A, Drawing FD.50 for approved standard fabrication and installation detail.
- **Verification of ceiling and wall conditions, in addition to coordination with the architect on sign placement, is required with nurse call lights, exit signs, other code-related signs, and obstructions.**
- **The need for additional structural support to be verified on project specific basis.**




Top View



Front View (Back View Similar)
Scale: 3"=1'-0"



Alternate Layout



Installation Context
Scale: 3/16"=1'-0"

Interior Identification

ID.50

Maintenance ID Tag

Usage

- Operationally required when room ID does not include architectural room number.
- Operationally required at all equipment alcoves and corridor thresholds.

Placement

- See installation context.

Components

- (A) Panel: 1/8" thick non-glare acrylic, subsurface painted; clear returns with smooth, finished milled edges
- (B) Graphics: subsurface digital printed copy
 - Typeface: Proxima Nova Condensed Medium

Colors & Materials




See Chapter 1: Universal Standards for detailed color and material specifications.

(C1) White Wonder

(D3) PMS Cool Gray 10C

Installation

- See Appendix A, Drawing FD.10 approved standard fabrication and installation detail.



Interior Identification

ID.51

Cubicle Workstation ID

Usage

- This sign type is used to identify employee cubicle workstations.

Placement

- On the exterior of the cubicle, adjacent to the point of entry.

Components

- (A) Front Panel: 1/8" thick non-glare acrylic with routed thumb notch
 - Finish: subsurface painted
 - Sides: no paint with clean routed edges
 - Window: remains clear for changeable insert
- (B) Graphics: subsurface UV cured digital print
 - Typeface: Proxima Nova Regular
- (C) Aluminum Laminate: 1/16" thick
 - Finish: satin brushed horizontal grain with eased edges

- (D) Back Panel: 3/16" thick acrylic backer, with milled out pocket (smooth edges with no visible milled markings) and routed thumb notch
 - Finish: subsurface painted
 - Sides: no paint with clean routed edges
- (E1) Attachment: fabric pins
- (E2) Attachment: VHB tape and silicone adhesive
- (F) Insert: paper insert with printed copy
 - Typeface: Proxima Nova Regular






Colors & Materials

See Chapter 1: Universal Standards for detailed color and material specifications.

- (C1) White Wonder (D3) PMS Cool Gray 10 (M3) Brushed Aluminum

Installation

- Fabric cubicles: mounted with fabric pins as shown below.
- Hard surface cubicles: mounted flush to finished surface with VHB tape and silicone adhesive or cubicle clips.
- See Appendix A, Drawing FD.20 for approved standard fabrication and installation detail.



Interior Identification

ID.52

Locker Number Tag

Usage

- This sign type is used to identify lockers.

Placement

- See installation context.

Components

- Ⓐ Panel: 1/8" thick non-glare acrylic, subsurface painted; clear returns with smooth, finished milled edges
- Ⓑ Graphics: subsurface digital printed copy
 - Typeface: Proxima Nova Condensed Medium



Colors & Materials

See Chapter 1: Universal Standards for detailed color and material specifications.


- Ⓒ1 White Wonder
- Ⓓ3 PMS Cool Gray 10C

Installation

- Locate odd numbers on top row of lockers, even numbers on bottom row.
- See Appendix A, Drawing FD.10 approved standard fabrication and installation detail.
- Align to the top of the handle.



Installation Context 1
Scale: 1/4" = 1'-0"



Installation Context 2
Scale: 1/4" = 1'-0"